Eugene E. Lundquist

# TECHNICAL NOTES

# NATIONAL ADVISORY COMMITTEE FOR AERONAUTICS

No. 527

STRENGTH TESTS OF THIN-WALLED DURALUMIN

CYLINDERS OF ELLIPTIC SECTION.

By Eugene E. Lundquist and Walter F. Burke Langley Memorial Aeronautical Laboratory

Washington May 1935

## NATIONAL ADVISORY COMMITTEE FOR AERONAUTICS

## TECHNICAL NOTE NO. 527

# STRENGTH TESTS OF THIN-WALLED DURALUMIN

CYLINDERS OF ELLIPTIC SECTION

By Eugene E. Lundquist and Walter F. Burke

## SUMMARY

This report is the fifth of a series presenting the results of strength tests of thin-walled cylinders and truncated cones of circular and elliptic section; it includes the results obtained from torsion tests on 30 cylinders, pure bending tests on 30 cylinders, and combined transverse shear and bending tests on 60 cylinders. All the cylinders tested were of elliptic section with the ends clamped to rigid bulkheads. In the pure bending and combined transverse shear and bending tests the loads were applied in the plane of the major axis.

The results of the tests on elliptic cylinders are correlated with the results of corresponding tests on circular cylinders and are presented in charts suitable for use in design.

## INTRODUCTION

As part of an investigation of the strength of stressed-skin, or monocoque, structures for aircraft, the National Advisory Committee for Aeronautics in cooperation with the Army Air Corps; the Bureau of Aeronautics, Navy Department; the National Bureau of Standards; and the Bureau of Air Commerce has made an extensive series of tests on thin-walled duralumin cylinders and truncated cones of circular and elliptic section. In these tests, the absolute and relative dimensions of the specimens were varied to study the types of failure and to establish useful quantitative data in the following loading conditions: torsion, compression, bending, and combined loading.

The first four reports of this series (references 1 to 4, inclusive) present the results obtained in the tests of thin-walled cylinders of circular section. This report

presents the results obtained in tests of thin-walled cylinders of elliptic section. In the tests of the elliptic cylinders the loading conditions were torsion, pure bending, and combined transverse shear—and bending. In the latter two loading conditions the loads were applied in the plane of the major axis.

#### MATERIAL

The duralumin (Al. Co. of Am. 17ST) used in these tests was obtained from the manufacturer in sheet form with nominal thicknesses of O.Oll, O.Ol6, and O.O22 inch. The properties of this material as determined by the National Bureau of Standards from specimens selected at random are given in references 1 and 2. As all the test cylinders failed by elastic buckling of the walls at stresses considerably below the yield-point stress, the modulus of elasticity E, which was substantially constant for all sheet thicknesses, is the only important property of the material that need be considered. For all cylinders an average value of E (10.4 × 10° pounds per square inch) was used in the analysis of the results.

## SPECIMENS

The test specimens were right elliptic cylinders with a semimajor axis of 7.5 inches and semiminor axes of 6.0 and 4.5 inches. The lengths varied from 3.75 to 22.5 The cylinders were constructed in the following First, a duralumin sheet was cut to the dimensions of the developed surface. The sheet was then wrapped about and clamped to end bulkheads. (See figs. 1, 2, and 3.) With the cylinder thus assembled, a butt strap 1 inch wide and of the same thickness as the sheet was fitted, drilled, and bolted in place to close the seam, which was always located at one end of the minor axis. In the assembly of the specimen, an effort was made to avoid having either a looseness of the skin (soft spots) or wrinkles in the walls when finally constructed. Actually this objective could not be attained at the ends of the minor axis where there was always a slight looseness of the skin which was more pronounced in the thinner sheets than in the thicker ones.

The end bulkheads, to which the loads were applied, were each constructed of two steel plates one-quarter inch

thick separated by a plywood core 1-1/2 inches thick. These parts were bolted together and machined to the specified outside dimensions. Steel bands approximately one-quarter inch thick were used to clamp the duralumin sheet to the bulkheads. These bands were machined to the same dimensions as the bulkheads.

# APPARATUS AND METHOD

The thickness of each sheet was measured to an estimated precision of ±0.0003 inch at a large number of stations by means of a dial gage mounted in a special jig. In general, the variation in thickness throughout a given sheet was not more than 2 percent of the average thickness. The average thicknesses of the sheets were used in all calculations of stress and radius-thickness ratio.

The loads were applied to the elliptic cylinders with the same apparatus used in the corresponding tests on circular cylinders. Descriptions and photographs of the apparatus used in the torsion, pure bending, and combined transverse shear and bending tests are given in references 1, 3, and 4.

# DISCUSSION OF RESULTS

The results of the tests on the elliptic cylinders are presented in tables I, II, and III as well as in certain figures discussed later.

Torsion.— The torque loads were applied in increments of about 1 percent of the estimated load at failure. After a few tests, however, the first increment of load was increased to about half the estimated load at first wrinkle. At first wrinkling one or more diagonal wrinkles began to form at the ends of the minor axis. With an increase in load these wrinkles grew steadily in size and number, spreading toward the ends of the major axis until failure occurred by a sudden increase in deformation and the formation of wrinkles in the complete circumference. (See fig. 1.)

Prior to wrinkling it seems reasonable to assume that the conditions of stress within the walls of the cylinder are in accord with the membrane analogy (reference 5).

After wrinkling has occurred, however, the conditions of stress are doubtful and probably vary with the degree of buckling.

By the membrane analogy

$$S = \frac{T}{2At} \tag{1}$$

where

- S, shearing stress in the skin.
- T, torque applied.

A=πab, area of the ellipse.

t, thickness of the sheet.

The shearing stress as given by equation (1) was calculated for each test cylinder at the conditions of first wrinkle and ultimate load. These stresses are used in plotting the experimental points in figure 4, which is the same type of chart used by Donnell in reference 6 for presenting the results of torsion tests on thin-walled cylinders of circular section. It will be noted that the experimental points for ultimate load plot between the theoretical curves and those recommended for design. As the data from torsion tests of circular cylinders also plot between these same curves (reference 6, fig. 1), it may be concluded that the shearing stress at ultimate load for an elliptic cylinder is the same as that for the circumscribed circular cylinder of the same sheet thickness and length. Actually the membrane analogy does not give a true picture of the stress condition at ultimate load but gives a shearing stress which lies between that at the ends of the semimajor and semiminor axes. It must therefore be regarded as an average shearing stress for the elliptic cylinder and analogous to the modulus of rupture in beams.

As the curvature of the sheet varies from a minimum at the ends of the minor axis to a maximum at the ends of the major axis, it is natural to expect that wrinkling prior to failure will occur in an elliptic cylinder subjected to torsion. In a perfectly constructed cylinder it is not likely that first wrinkling would occur until the shearing stress reaches or exceeds So, the shearing stress at failure for a circular cylinder of the same sheet thickness and length but with a radius equal to the

radius of curvature at the ends of the minor axis. The effect of imperfections, which are always present, is to cause a premature wrinkling. Consequently, the shearing stress at first wrinkle S<sub>w</sub> was divided by S<sub>o</sub> and the ratio plotted as a percentage in figure 5. With the exception of one point, all of the results plot below 100 percent. This figure is analogous to figure 10 of reference 1.

When calculating the value of So for the points in figure 5, the equation given in reference 1 was used because it is more representative of the technic used in this series of tests. For general design, the equations given in reference 6 are recommended.

Pure bending. In the pure bending tests the loads were applied in the plane of the major axis of the ellipse. As in the torsion tests, the loads were applied in increments of about 1 percent of the estimated load at failure. In the case of the 0.8 ellipse  $\left(\frac{b}{a}=0.8\right)$ , wrinkling did not usually occur prior to failure. Failure is defined as the complete collapse of the compression side of the cylinders with the formation of diamond-shaped wrinkles. (See fig. 2.) In the case of the 0.6 ellipse  $\left(\frac{b}{a}=0.6\right)$ , preliminary wrinkles usually formed prior to failure. These wrinkles always appeared at about two thirds of the distance from the neutral axis to the extreme fiber.

The reason for preliminary wrinkles forming prior to failure in the 0.6 ellipse and not in the 0.8 ellipse is shown qualitatively in figure 6. The critical compressive stress for any element is approximately proportional to the curvature, and hence to the abscissa, of the solid curves in figure 6. In a cylinder subjected to pure bending the actual stress varies linearly from the neutral axis to the extreme fiber. When the loading has reached such a point that the actual stress is approximately that shown by the dotted lines, first wrinkling is likely to occur at the point where the solid and dotted curves touch. For the 0.6 ellipse, the elements at the extreme fiber are capable of resisting a much higher stress than indicated by the dotted line with the result that failure is delayed until a much higher load is reached. For the 0.8 ellipse failure tends to occur at or soon after first wrinkling because the elements on the extreme fiber and for a considerable distance toward the neutral axis are not capable of resisting any large increase in stress.

In the presentation of the results of the pure bending tests, it has been assumed that the ordinary theory of bending applies and that the stress on the extreme compression fiber at failure is given by the equation

$$s_b = \frac{Mc}{I} = \frac{M}{k_b a^2 t} \tag{2}$$

where I is the bending moment applied in the plane of the major axis of the ellipse

a, the semimajor axis of the ellipse

and k<sub>b</sub>, a nondimensional coefficient that varies with the eccentricity of the ellipse. (See fig. 7.)

The stress on the extreme fiber at failure as given by equation (2) is comparable with the corresponding stress calculated for the pure bending tests on circular cylinders (reference 3) and, for comparison, is plotted in a like manner in figure 8. Inspection of this figure shows that the stress on the extreme fiber at failure increases with decrease in the ratio b/a. The increased strength for the more eccentric ellipse is obviously caused by the greater stability of the more sharply curved portion at the end of the major axis where the fibers are more highly stressed. It will be noted in figure 8 that the results of the tests of elliptic cylinders scatter almost as widely as do the results of the tests of circular cylinders. The designer in using these data may therefore choose strength values more or less conservatively, as desired.

Combined transverse shear and bending .- The loads in the transverse shear and bending tests were applied in the plane of the major axis of the ellipse in increments of about I percent of the estimated load at failure. When the position of the transverse load was such that the ratio of moment to shear was small, failure occurred by shear. Prior to failure, diagonal shear wrinkles formed on the sides of the cylinder. With an increase in load, these wrinkles grew steadily in size until failure occurred by a collapse of the outermost compression elements. When the position of the transverse load was such that the ratio of moment to shear was large, failure occurred by bending in the same manner as in the pure bending tests. When the ratio of moment to shear had an intermediate value, failure occurred by a combination of shear and bending. (See photographs of cylinders after failure, fig. 3.)

The variation of the bending stress at failure with the ratio of moment to shear is studied for each of the following groups of cylinders tested.

Group	<u>b</u> a	<u>length</u> a	a t	Nominal sheet thickness
				Inch
1	0.8	0.50	630 - 682	0.011
2	.6	• 50	<b>6</b> 25 <b>-</b> 688	.011
3	.8	1:00	658 - 707	.011
4	•6	1.00	658 - 721	.011
5	•6	2.00	630 - 682	.011
6	.8	2.00	630 - 682	.011

For each group, the results of the tests are presented in a manner similar to that used for the corresponding tests on circular cylinders (reference 4). In figure 9 the nondimensional parameter  $\frac{M}{r\,i\,V}$  represents the loading and stress conditions and is therefore analogous to  $\frac{M}{r\,V}$  in reference 4. The value of  $r^i$  was so chosen that for the elliptic cylinder

$$\frac{M}{r!V} = \frac{f_b}{f_v} \tag{3}$$

where fb and fv are the bending stress on the extreme fiber and the shearing stress at the neutral axis respectively as given by the following equations derived by the ordinary theory of bending

$$f_b = \frac{u}{k_b a^2 t} \tag{4}$$

$$f_{V} = \frac{V}{k_{V} * t} \tag{5}$$

In equation (5) V is the transverse shear in the plane of the major axis of the ellipse and  $k_{V}$  a nondimensional coefficient that varies with the eccentricity of the ellipse. (See fig. 7.)

In figure 9 lines a and b represent the upper and lower limits of the strength in pure bending. These limiting values show the dispersion of the results of the pure bending tests and were obtained for elliptic cylinders of the average a ratio in each group by interpolation of the results plotted in figure 8. At large values of  $\frac{M}{r!V}$  the bending-stress diagrams approach lines and b as an upper limit but with a tendency to plot just below them in some cases. (See fig. 9a, in particular.) The tendency for the bending-stress diagrams to plot below lines a and b seems to be more pronounced for the 0.8 than for the O.6 ellipse although the test data are not sufficiently extensive to draw a definite conclusion. the 0.8 ellipse in pure bending the elements on the extreme fiber and for a considerable distance toward the neutral axis tend to reach a condition of incipient failure at about the same time; whereas the 0.6 ellipse seems to have the capacity of supporting an increased load after first wrinkling. (See fig. 6.) It is therefore probable that the reduced bending strength in combined transverse shear and bending is caused by the presence of shear which might conceivably affect the strength of the 0.8 ellipse more than the strength of the O.6 ellipse. In any case, it appears that the lower limit of the strength in pure bending is a good value to use for the bending strength of thin-walled elliptic cylinders in combined transverse snear and bending at large values of  $\frac{H}{r!V}$ .

At small values of  $\frac{H}{r^{\dagger}V}$  failure occurred by shear. For comparison of the strength in transverse shear with the strength in torsion, lines c and d have been drawn in figure 9 representing the probable upper and lower limits for shear failure. These lines were drawn by plotting the equation

$$\frac{\mathbf{f}_{\bar{\mathbf{b}}}}{\bar{\mathbf{E}}} = \frac{\mathbf{S}}{\bar{\mathbf{E}}} \frac{\mathbf{H}}{\mathbf{r}^{\dagger} \bar{\mathbf{v}}} \tag{6}$$

and the second of the second o

Equation  $(\underline{6})$  is obtained from equation (3) by transposing terms, dividing by E, and substituting S for

fy, where S is the average shearing stress at failure for an elliptic cylinder in torsion. The lines c and d for shear failure in figure 9 are shown for the two values of S obtained from figure 4 for the largest and smallest sheet thickness for each group of cylinders. When reading values from figure 4 a straight line was imagined to be drawn through the experimental points for the elliptic cylinders of 0.011-inch nominal sheet thickness.

Inspection of figure 9 shows that the bending-stress diagrams at the very low values of  $\frac{M}{r^{\dagger}V}$ , corresponding to shear failure, plot above lines c and d. As in the case of circular cylinders (reference 4), this fact indicates that the transverse shearing stress on the neutral axis at failure is higher than the shearing stress at failure in torsion. Consequently, in a like manner the ratio of the two stresses  $\frac{f_V}{S}$  is plotted against  $\frac{M}{r^{\dagger}V}$  in figure 10 for each of the tests. It will be noted that as  $\frac{M}{r^{\dagger}V}$  approaches 0 the ratio  $\frac{f_V}{S}$  approaches a value between 1.2 and 1.48. Thus, if  $S_V$  is the shearing stress on the neutral axis at failure in pure transverse shear and S is the shearing stress at failure for a cylinder of the same dimensions in torsion,  $S_V$  and S may be related by the following approximate equation

$$S_{\nabla} = 1.25 \text{ s} \tag{7}$$

The coefficient 1.25 is somewhat conservative but its use is recommended so that the same relationship will hold for both elliptic and circular cylinders. (See reference 4, equation (5).)

At intermediate values of  $\frac{R}{r!\,V}$ , near the intersection of lines a and b with lines c and d in figure 9, there is a transition from shear to bending failure. As the point of transition is approached, there seems to be developed an increased strength similar to that shown by elastic theory when the number of waves in the buckled pattern changes from n to  $(n\pm 1)$ . The increased strength at the transition seems to be confined to a small range of  $\frac{R}{r!\,V}$  and is not always developed in the tests. For practical considerations, it therefore seems that the transition

from shear to bending failure can be given by the design chart for circular cylinders presented in reference 4 if  $\frac{M}{rV}$  is replaced by  $\frac{R}{rV}$ . With this change, the design chart for elliptic cylinders is given in figure 11. The solid curves in figure 9 were obtained from this chart using in one case the value of  $\frac{Sb}{SV}$  corresponding to lines a and c and in the other case the value corresponding to lines b and d. An inspection of the figures for the different groups indicates that, except for the increased strength previously discussed, these two curves represent quite well the limits of the experimental data in the transition from shear to bending failure.

In order to use the curves of figure 11 in design, it is necessary to know the loading condition  $\frac{M}{r!\,V}$  and to be able to predict the values of  $S_b$  and  $S_V$  for the olliptic cylinder. If these three quantities are known, the maximum allowable moment and/or stress on the extreme fiber can be read from the chart as a percentage of that for pure bending. The strength in shear then need not be investigated because its effect has been taken into account by a reduced bending strength.

When checking the strength of any section between adipacent bulkheads, the largest value of  $\frac{M}{r!\,V}$  in that section should be used to enter the chart of figure 11. This procedure tends toward conservatism and is certainly justified by the wide scattering of the test data.

## CONCLUSIONS

- 1. In torsion, the shearing stress at failure for thin-walled elliptic cylinders was found to be equal to the shearing stress at failure for circumscribed circular cylinders of the same sheet thickness and length. Because, buckling of the walls occurred at the onds of the minor axis prior to failure, the shearing stress calculated for the elliptic cylinder must be regarded as analogous to the modulus of rupture and so used in strength calculations.
  - 2. For pure bending in the plane of the major axis,

the calculated stress on the extreme fiber at failure was greater than the corresponding stress for circumscribed circular cylinders of the same sheet thickness and length. As in the case of circular cylinders, it was found that slight imperfections caused the test results to scatter widely. In view of this scattering, the bending strength must be considered somewhat indefinite and should therefore be estimated after consideration of all the experimental data for both elliptic and circular cylinders. Design values may then be chosen more or less conservatively as desired.

3. For combined transverse shear and bending in the plane of the major axis, the strength was dependent upon the loading condition as described by the term  $\frac{M}{r^{\frac{1}{2}}V}$ . At small values of  $\frac{M}{r^{\frac{1}{2}}V}$ , failure occurred in shear and, as  $\frac{M}{r^{\frac{1}{2}}V}$  approached zero (a condition of pure transverse shear), the shearing stress on the neutral axis at failure as calculated by the ordinary beam theory was approximately 1.25 times the shearing stress at failure in torsion.

At large values of  $\frac{M}{r^{\frac{1}{2}}}$ , failure occurred in bending and the strength developed was approximately equal to the lowest strengths developed for cylinders of the same dimension in pure bending.

At intermediate values of  $\frac{M}{r!\,V}$ , there was a transition from shear to bending failure. For use in calculating the strength of elliptic cylinders in combined transverse shear and bending it was found that a chart previously derived for circular cylinders may be used.

Langley Memorial Aeronautical Laboratory,
National Advisory Committee for Aeronautics,
Langley Field, Va., April 2, 1935.

## REFERENCES

- 1. Lundquist, Eugene E.: Strength Tests on Thin-Walled Duralumin Cylinders in Torsion. T.N. No. 427, N.A.C.A., 1932.
- 2. Lundquist, Eugene E.: Strength Tests of Thin-Walled Duralumin Cylinders in Compression. T.R. No. 473, N.A.C.A., 1933.
- 3. Lundquist, Eugene E.: Strength Tests of Thin-Walled Duralumin Cylinders in Pure Bending. T.N. No. 479, N.A.C.A., 1933.
- 4. Lundquist, Eugene E.: Strength Tests of Thin-Walled Duralumin Cylinders in Combined Transverse Shear and Bending. T.N. No. 523, N.A.C.A., 1935.
- 5. Timoshenko, S.: Strength of Materials, Part II. 1930, p. 623. D. Van Nostrand Co., Inc.
- 6. Donnell, L. H.: Stability of Thin-Walled Tubes Under Torsion. T.R. No. 479, N.A.C.A., 1933.

TABLE I

RESULTS OF TORSION TESTS ON ELLIPPIC CYLINDERS For all cylinders, Poisson's ratio  $\mu=0.3$   $\frac{b}{a}=0.8$ 

				ಣೆ			
Specimen No.	<b>-</b>	1	E	<b>ω</b>	(1-12) S 12	$\sqrt{1-\mu^2} \frac{l^3}{t^4}$	Remarks
	in.	in.	lbin.	lb./sq.in.			
648	0.0104	3.75	5510	1875	21.4	0.98	First wrinkle
			7790	2650	30.2		Failure
231	.0117	7.50	571.0	1730	62.3	306.0	First wrinkle
			6150	1360	67.0		Failure
283	.01.15	11,25	3900	1,200	100,5	700.0	First wrinkle
	- <del>-</del>		4860	1496	125,3		Failure
285	.0113	15.00	2220	694	107,1	1274.0	First wrinkle
			4000	1250	193,0		Tailure
287	.0116	22,50	2100	6.40	211.0	2780.0	First wrinkle
			3720	1133	373.0		Failure
309	.0158	3.75	15300	34,25	16.9	56.6	First wrinkle
			19260	.1210	21,3		Failure
311	.0162	7,50	0996	21.10	39,5	221.0	First wrinkle
			13980	3050	57.2		Failure
313	.0162	11.25	9512	2080	87.8	497.0	First wrinkle
			11760	2570	103.5		Failure
315	1910"	15.00	3920	856	65.0	890.0	First wrinkle
			10440	2295	174.4		Failure
317	.0160	22.50	71.20	1575	272.0	2010.0	First wrinkle
			8180	1810	313.0		Failure
349	.0241	3,75	43488	6380	13,5	57.1	First wrinkle
			18488	71.10	15,1		Failure
351	.0246	7.50	29488	4240	34,5	145.5	First wrinkle
			32288	4640	37.8		Failure
353	.0237	11.25	20408	, 3050	8.09	339.5	First wrinkle
			23088	3440	67.8		Failure

TABLE I (Cont.)  $\frac{b}{a} = 0.8$ 

				8.0 = 0.8	7 - 2 - 2 - 2 - 2 - 2 - 2 - 2 - 2 - 2 -		
Specimen No.	+->	1	EH	ഹ	$(1-\mu^3)\frac{S}{\pi}\frac{1}{t^2}$	$\sqrt{1-\mu^2} \frac{l^2}{t^4}$	Remarks
	in,	in.	1bin.	lb./sq.in.			
355	0.0247	15.00	14408	2060	66.5	580.0	First wrinkle
357	.0240	22,50	17868	2635 2740	203.0	1342.0	First wrinkle
			0	b 6 = 0.6	0		יי יין נידי פ
280	0.0104	3.75	331.0	1502	17.1	0.98	First wrinkle
	1	i	6790	3080	35.1	•	Fei lure
282	.0114	7.50	1900	787	000 000 000 000	314.0	First wrinkle
284	.01.15	11.25	1860	763	63.0	700.0	Frst wrinkle
			3740	1533	128.4		Failure
286	.01.14	15.00	2100	870	131.6	1263.0	First wrinkle
			3200	1325	200.5		Fuilure
288	•0116	22,50	2140	178	287.0	2780.0	First wrinkle
			2880	1170	385.0		Failure
310	.0157	3.75	9260	2785	13.9	57.0	First Wrinkle
			16700	0109	25.0		Failure
312	.0167	7,50	7660	2165	38.2	21.4.0	First wrinkle
	-		11960	3375	59.6		Failure
314	.0159	11,25	5120	1520	9•99	506.0	First wrinkle
			8480	2520	110.3		Failure
316	.0161	15.00	6320	1853	140.7	0.068	First wrinkle
			7720	2265	172.0		Failure
318	.0161	22.50	5720	1678	287.0	2000.0	First wrinkle
-			6520	1910	327.0		Failure
350	.0238	3.75	27488	5445	11.8	37.6	First wrinkle
<del></del>		_	35328	2000	15,2		Failure

TABLE I (Cont.)

The state of the s	$\frac{l^2}{t^d}$ Remarks		5   First wrinkle	Failure		-		Failure	O   First wrinkle	Failure	
	$\sqrt{1-\mu^2} \frac{l^a}{t^a}$		1.52,5		339.5		590.0		1370.0		
	(1-12) S 1:25		36.7	44.9	48.7	9.0%	80.4	111.0	1.75.0	220.0	
$\frac{b}{a} = 0.6$	ಬ	lb./sq.in.	4110	5030	2470	3580	2410	3325	2180	2745	
	E-I	1bin.	20488	25048	12407	18008	12408	17128	10868	13708	
	1	in.	7,50		11,25		15.00		22,50		
	- حړ	in.	0.0235		.0237		.0243		.0235		
	Specimen No.		352		354		356		358		_

TABLE II

RESULTS OF PURE BENDING TESTS ON ELLIPTIC CYLINDERS SHOWING CORRECTIONS MADE FOR THE EFFECT OF A SMALL TENSION P ON THE SPECIMEN

 $\frac{\overline{o}}{8} = 0.8$ 

						ಕ.				
Spec.	4	a t	t	P	М	Stress caused by ten- sion P	fb	s <sub>b</sub>	S <sub>D</sub> E	R emarks
	in.		in.							
290	0.0110	! 682	3.75	93.0	11335	! : 198	6820	6622	0.000637	   Failure
291	.0113			•	13305	173	7790	ì	.000732	l .
293			11.25			173	6410	1	,	First wrinkle
					11185		6550	t		Failure
295	.0110	682	15.00	76.0	6935	162	4172	:	(	First Wrinkle
				! !	10635		6400	6238	.000600	Failure
297	.0110	682	22.50	74.0	8535	158	5135	4977	.000479	First wrinkle
			1	}	11055	<b>:</b> :	6650	6492	.000624	Failure
307	.0166	+			28855	113	11510	11397	.001096	Failure
305	.0161	i	1		22355	116	9185		.000872	
303	.0164	457	11.25	80.0	23175	114	9360			First wrinkle
					27055	[		10816	.001040	Failure
301	.0167	449	15.00	74.0	<u>.</u>	104	10970	1	,	First wrinkle
			ļ Ī		28915		11470		.001093	Failure
299	1	i	22.50			103	9530		.000907	Failure
339	.0245	1	3.75			91	ľ	15974	.001536	Failure
341	.0252			95.0	62195	88	16335		.001562	Failure
343			11.25			82	15880		.001520	Failure
345			15.00			70		15915	.001531	Failure
347	.0234	32U	22.50	74.0	22312	74	14810	14736	.001417	Failure
						$\frac{b}{a} = 0$	.6			
289	0.0110	682	3.75	87.0	9595	207	6910	6703	0.000644	First wrinkle
			i		11255		8110	7903	.000760	Failure
292	.0107	701	7.50	77.5	9965	190	7385	7195	.000692	First wrinkle
					11165		8270	8080	.000777	Failure
294	.0113	664	11.25	77.5	9645	180	6765	6585	.000633	First wrinkle
		į			13025	i	9140		.000861	Failure
296	.0110	682	15.00	70.0	9135	166	6585			First wrinkle
		_			11955		8620	8454	.000813	Failure
298			22.50			162	8180	8018	.000771	Failure
308	.0168	446	3.75	1	29775	115	14050		. 1	First wrinkle
700	67.5				31935	}	15085		.CO1439	Failure
306	.0163	460	7.50		23415	119	11400			First wrinkle
	:	1	;	ì	26395	}	12855	12736	.001224	Failure

TABLE II (Cont.)  $\frac{b}{a} = 0.6$ 

Spec.	t	<u>a</u>	ī	P	М	Stress caused by ten- sion P	fb	Sъ	S <sub>d</sub> E	Remarks
	in.		in.							
304 302	0.0167	•	•		28995 27615	116 105		13674 12935	0.001315	
300	.0169	1 1	22.50		24675	105	11590	11485	.001104	First wrinkle
340	.C240	1	t	1 - :	28015 57015	97	18850	13055 18753	.001803	Failure
342 344	.0248 .0234	; -			61075 51415	94 85		19456 17365	.001871	Failure  First wrinkle
346	.0245	306	15.00	68.0	51815 58995	73		17495 19037	.CO1682	
348	.0236	318	22.50	68.0	45075 49275	75 ·		15075 16490	.001449 .001586	First wrinkle Failure

TABLE III RESULTS OF COMBINED TRANSVERSE SHEAR AND BENDING TESTS ON ELLIPTIC CYLINDERS Group 1  $\frac{b}{} = 0.8$  r! = 6.48  $\frac{1}{} = 0.50$ 

Group	) 1	a	= (	J.8	r' =	6.48	a	= 0.50	
Spec.	t	a. t	٧	М	Ϊγ	ĨЪ	r'V	ਜ਼ੀ ਰਿ	Remarks
	in.		lb.	lbin.	lb./sq.in.	lb./sq.in.			
379	0.0119	630	569	2558	2072	1423	0.69	0.000137	First Wrinkle
381	.0113	664	1122 459	5323 4288	4085 1756	2962 2510	.73 1.44	.000285 .000241	Failure First wrinkle
383	.0113	664	807 437	7420 6283	3090 1672	4345 3680	1.42 2.22	.000418 .000354	Failure First wrinkle
385	.0119	530	719 452	9943 9203	2752 1645	5822 5170	2.12 3.17		Failure First Wrinkle
387	.0111	676	680 244	13403 7320	2475 953	7460 4370	3.03 4.63	.000718 .000420	Failure First wrinkle
389	.0111	676	415 175	11260 7158	1619 683	6720 4272	4.16 6.31	.000645 .000411	Failure First wrinkle
391	.0115	652	307 197	10858 8723	1198 742	6480 5025	5.45 6.83		Failure First wrinkle
393	.0117	641	253 83	10563 5954	953 307	6080 3370	6.42		Failure First wrinkle
395	.0110	682	207 139	10654 9423	766 547	6040 5670	7.94 10.47	.000581	Failure First wrinkle
397	.0110	682	161 123	10353 9971	63 <u>4</u> 484	6230 6000	9.87 12.42	.000599	Failure Failure

TABLE III (Cont.)

Group	2	<u>ხ</u> გ	= 0.	6	r! = ;	5.60	<u>l</u> =	= 0.50	
Spec. No.	t	<u>a</u> t	V	М	$\mathtt{f}_{\mathtt{v}}$	īв	M riv	fb E	Remarks
380	0.0120	625	lb. 463	lbin. 2027	lb./sq.in. 1710	lb./sq.in. 1341	0.78	0.000129	First wrinkle
382	.Cl14	1	1219 513	5807 4749	4505 1994	3840 3305	.86 1.65	.000370 .000318	Failure First Vrinkle
384	.0114	658	869 480	7953 6790	3380 1866	5535 4727	1.64 2.52	.000532 .000455	Failure First wrinkle
386	.0119	630	815 293	11152 63 <b>4</b> 2	3170 1092	7765 4230	2.46 3.87	.000747 .000407	Failure First wrinkle
388	.0112	670	7C7 343	13812 9484	2636 1357	9210 6725	3.51 4.94	.000886 .000647	Failure First Wrinkle
390	.0111	676	381 313	10359 10887	1507 1250	7340 7785	4.89 6.21	.000706 .000749	Failure First wrinkle
392	.0115	652	413 113	13687 5782	1650 436	9790 4000	5.95 9.14	.000941 .000385	Failure First Wrinkle
394	.0115	652	330 247	12942 11983	1272 953	8935 8280	7.04 8.66	.000858 .000796	Failure First Wrinkle
396	.0109	688	275 155	13053 9882	1060 630	9010 7180	8.53 11.38	.000866	Failure First wrinkle
398	.0111	676	205 133	12022 10200	834 532	8755 7300	10.52 13.70	.000842	Failure First wrinkle
			173	12100	692	8650	12.55	.000832	Failure

TABLE III (Cont.)

Grou	э 3 	<u>p</u>	<b>=</b> (	3.8	r¹ =	6.48	<u>ī</u> a	= 1.0	
Spec.	t	al t	V	M	f <sub>⊽</sub>	fъ	MrIV	fb E	Remarks
	in.		lb.	lbin.	lb./sq.in.	lb./sq.in.			
319	0.0106	707	271	2004	1106	1252	1.14	0.000120	First Wrinkle
321	.0113	664	551 491	4384 5670	2250 1880	2738 3323	1.22	.000264	Failure First
			647	7454	2478	4367	1.76	.000420	Wrinkle Failure
323	.0106	707	258	4284	1054	2677	2.56	.000257	First Wrinkle
325	.0106	707	537 279	8474 6162	2192 1139	5295 3850	2.42 3.41	.000509	Failure First wrinkle
327	.0112	670	420 403	8843 10570	1715 1557	5525 6250	3.22 4.05	.000532	Failure First
329	.0106	707	413 195	10806 6759	1596 796	6420 4220	4.00 5.35	.000614 .000406	wrinkle Failure First
331	.0114	658	268 145	6728 6437	1C94 551	5453 3738	5.00 6.86	.000525	wrinkle Failure First
001	• • • • • • • • • • • • • • • • • • • •		271	10337	1029	6000	5.85	.000578	wrinkle Failure
333	.0107	7Cl	211	9765	854	6045	7.14	.000582	First wrinkle
335	.0114	658	215 213	9905 11521	871 810	6130 6700	7.07 8:34	.000590 .000644	Failure First
337	.0107	7Cl	217 77	11685 7490	825 312	6785 4636	8.26 15.01	.000653 .000446	wrinkle Failure First
			83	7780	336	4815	14,40	.000463	wrinkle Failure

TABLE III (Cont.)

Grou	p 4	<u>b</u> a	= 0	.6	r; =	5.60	$\frac{1}{a}$	= 1.0	
Spec No.	t	a t	٧	М	f <sub>V</sub>	fb	M r I V	$\frac{f_{b}}{E}$	Remarks
	in.		15.	lbin.	lb./sq.in.	lb./sq.in.			
320	0.0113	664	367	2820	1439	1979	1.37	0.000190	First
	Ì		700	5655	2746	3970	1.45	.000382	Failure
322	.0106	707	307	3535	1283	2647	2.06	.000255	First
	Į		595	6855	2488	5130	2.07	.000493	wrinkle Failure
324	.0104	721	267	4680	1223	3570	2.91	.000433	First
0.0 1	.0.01	.~_	~C.	1000	1~20	02.0	~	.0000	wrinkle
			537	8435	2288	6435	2.81	.000619	Failure
326	.0105	714	221	4993	932	3770	4.03	.000363	First
									wrinkle
328	0177	~ ~ 1	417	8723	1759	6590 5565	3.75	.000634	Failure
328	.0113	664	292	7931	1145	5565	4.85	.000535	First wrinkle
			512	12996	2008	9125	4.55	.000878	Failure
330	.0106	707	327	10210	1367	7650	5.57	.000736	First
			[						wrinkle
i			381	11668	1593	8740	5.49	.000840	Failure
332	.0114	658	297	11008	1154	7660	6.61	.000737	First
l			700	77000	3500	0670	6 50	22222	wrinkle
334	.0105	77.4	388 203	13829	1508	9630 7050	6.39	.000926	Failure
304	•OTCB	(14)	200	9336	856	7050	8.21	.000678	First wrinkle
		Ì	241	10656	1016	8050	7.94	.000775	Failure
336	.0114	658	219	11572	852	8060	9.42	.000775	First
		l	i			_			wrinkle
-		-	242	12515	941	8710	9.28	.000838	Failure
338	.0105	714	91	7931	384	5990	15.55	.000576	First
ļ			7.00	2442	-3-	~~ a	- 05		wrinkle
l	j	i	122	9448	515	7180	13.90	.000687	Failure

TABLE III (Cont.)

Group	5	<u>b</u> a	= (	0.8	r! =	6.48	$\frac{l}{a}$	= 2.0	
Spec.	t	a t	V	М	f <sub>v</sub>	fb	M r T T	f <sub>b</sub> E	Remarks
	in.		lb.	lbin.	lb./sq.in.	lb./sq.in.			
359	0.0119	630	437	6137	1590	3415	2.17	0.000328	First Wrinkle
		1	527	7487	1919	• 4168	2.18	.000401	Failure
361	.0116	647	502	2514	1873	1434	.77	.000138	First
		1							wrinkle
		1	521	2652	1945	1513	.78	.000146	Failure
363	.0110	682	270	2487	1062	1496	1.42	.000144	First
			4.45	4500	7845	0844	7	22224	wrinkle
		1 0	443	4562	1745	2744	1.58	.000264	Failure
365	.0110	682	251	4424	987	2662	2.72	.000256	First
ĺ			409	7275	1610	4700	ח דר	000433	wrinkle
367	.0118	C7C	4C7	9822	1493	4380 5510	2.73 3.72	.000422 .000530	Failure First
307	•0770	0.00	4C /	3022	7.420	SOLO .	0.12	.000050	wrinkle
			423	10222	1552	5740	3.73	.000552	Failure
369	.0110	682	313	9767	1232	5880	4.79	.000566	Failure
371	.0114	. ,	307	11701	1166	6800	5.88	.000500	First
0.1			00,		2200		6,00	.000002	wrinkle
	!		315	11941	1196	6935	5.83	.000667	Failure
373	.0113	1 1	269	12351	1029	7235	7.05	.000696	Failure
375	.0111		140	8582	546	5120	9.46	.000492	First
ļ									wrinkle
			161	9482	629	5660	9.05	.000544	Failure
377	.0114	658	192	11914	729	6920	9.58	.000665	First
1		1							wrinkle
ļ	ļ	;	194	12014	737	6980	9.50	.000671	Failure

TABLE III (Cont.)

Grou	6	<u>b</u>	= (	0.6	r! =	5.60	$\frac{l}{a}$	= 2.0	
Spec. No.	t	a t	▽	М	$\mathtt{f}_{\mathtt{v}}$	fb	$\frac{M}{r^{1}V}$	f <sub>b</sub> E	Remarks
	in.	ļ	lb.	lbin.	lb./sq.in.	lb./sq.in.			
360	0.0119	630	383	5332	1428	3555	2.49	0.000342	First wrinkle
362	.0114	658	498 323	7052 1222	1857 1256	4700 851	2.54 .68	.000452	Failure First Wrinkle
364	.0111	676	501 213	2557 1827	1949 851	1780 1306	.92 1.53	.000171 .0001 <i>2</i> 6	Failure First wrinkle
366	.0111	676	433 291	3867 5134	1730 1162	2764 3670	1.60 3.15	.000266 .000353	Failure First Wrinkle
368	.0119	630	42 <u>4</u> 343	7534 8307	1694 1278	5388 5540	3.19 4.32	.000518 .000533	Failure First Wrinkle
370	.0110	682	447 181	10727 6012	1666 729	7155 <del>4</del> 333	4.32 5.93	.000688 .000416	Failure First wrinkle
372	.0116	647	348 217	10662 8626	1402 830	7690 5910	5.49 7.10	.000740	Failure First Wrinkle
374	.0114	658	283 222	10456 10446	1082 862	7155 7270	6.64 8.39	.000688 .000700	Failure First wrinkle
376	.0111	676	307 215	13686	1194 858	9530 8310	8.00 9.65	.000916 .000800	Failure First Wrinkle
378	.0114	658	245 217	12877 12939	979 8 <del>44</del>	9210 9010	9.45 10.70	.000885 .000866	Failure Failure










Figure 2.-Elliptic cylinders after failure in pure bending.





<u>p</u> = 0.6

**ं वं** 0 ः व

Figure 3.-Side view of elliptic cylinders after failure in combined transverse shear and bending. (Photographs show the transition from shear to bending failure as M/r'V varies from small to large values).

7.74







Figure 4. - Shearing stress at failure S for elliptic cylinders in torsion.










21,000






Figure 9a. - Bending-stress diagrams for elliptic cylinders in combined transverse shear and bending.




Figure 9b.- Bending-stress diagrams for elliptic cylinders in combined transverse shear and bending.




Figure 9c.- Bending-stress diagrams for elliptic cylinders in combined transverse shear and bending.




Figure 9d. - Bending-stress diagrams for elliptic cylinders in combined transverse shear and bending.




Figure 9e.- Bending-stress diagrams for elliptic cylinders in combined transverse shear and bending.




Figure 9f.- Bending-stress diagrams for elliptic cylinders in combined transverse shear and bending.




Figure 10a.—Shearing—stress diagrams for elliptic cylinders in combined transverse shear and bending.




Figure 10b.-Shearing-stress diagrams for elliptic cylinders in combined transverse shear and bending.



